

**MARYLAND HISTORICAL TRUST
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes ☐
no ☐

Property Name: Winter/O'Donnell Farm, (aka Jenkins Brick House) Inventory Number: AL-VI-B-031
Address: 13001 O' Donnell Lane SW City: Frostburg Zip Code: 21502
County: Allegany USGS Topographic Map: Lonaconing
Owner: William Jenkins Is the property being evaluated a district? ☐ yes
Tax Parcel Number: Unknown Tax Map Number: 35 Tax Account ID Number: Unknown
Project: _____ Agency: _____
Site visit by MHT Staff: ☒ no ☐ yes Name: _____ Date: _____
Is the property located within a historic district? ☐ yes ☒ no

If the property is within a district

District Inventory Number: _____

NR-listed district ☐ yes Eligible district ☐ yes District Name: _____

Preparer's Recommendation: Contributing resource ☐ yes ☐ no Non-contributing but eligible in another context ☐

If the property is not within a district (or the property is a district)

Preparer's Recommendation: Eligible ☒ yes ☐ no

Criteria: ☐ A ☐ B ☒ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None

Documentation on the property/district is presented in:

The Winter/O'Donnell House is located on O'Donnell Lane, 0.3 miles east of Cabin Run Road in the Georges Creek Valley in Frostburg, Allegany County, Maryland. The dwelling is an excellent example of brick vernacular architecture. The building was surveyed in 1976 and a Maryland Historical Trust Inventory Form for State Historic Sites Survey was completed for the property under the name Jenkins Brick House (AL-VI-B-031). The inventory form notes that the property is "located among an architecturally significant group of farm houses located in the upper George's Creek Valley." The Winter/O'Donnell House faces southeast and overlooks rolling hills and forested areas to the west and south. Open pasture land is visible to the north of the property.

Dwelling Description

The ca. 1829 Winter/O'Donnell House is a two-story, five-bay wide, side-gabled, rectangular shaped vernacular-style dwelling that rests on a stone foundation of random ashlar with flush joints. The dwelling is constructed with brick and features a Flemish bond pattern on the front elevation and American Common bond pattern with five

MARYLAND HISTORICAL TRUST REVIEW

Eligibility recommended ☐ Eligibility not recommended ☒
Criteria: ☐ A ☐ B ☐ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None
Comments: lost integrity through additions and alterations

James O. Apple
Reviewer, Office of Preservation Services

1/14/10

Date

[Signature]
Reviewer, NR Program

1/14/10

Date

20100266

MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM

Continuation Sheet No. 1

AL-VI-B-031

rows of stretchers between each row of headers on the remaining three elevations. Six-over-six light, double-hung sash replacement windows are visible on the front (east) elevation.

The front (east) elevation features a corbelled brick frieze located under the eaves. Two entrances, both with new metal entry and storm doors, are protected by a new, full-width, five-bay, shed-roof porch that is supported by square wood columns. Four-light transoms are visible above both doors. Six-over-six-light, double-hung sash replacement windows are visible on the front (east) and rear (west) elevations. The doors and first-floor windows are topped and highlighted with a brick solder course. On the south elevation, a single entry door is sited on the southeast corner of the stone foundation. Two corbelled, brick, flush-end chimneys are visible on the dwelling on the north and south elevations. There are no windows on these elevations. Attached to the south elevation is a raised wood projection that is accessed by sliding doors and is supported by wood posts. Wood stairs on the south elevation lead to the porch and entrances on the front elevation.

Attached to the rear of the dwelling is a two-story, four-by-two bay, gable roof, ca.2000 addition that is positioned on an east/west axis (personal interview). The addition has been constructed using similar materials and workmanship identical to the original portion of the dwelling. The addition is constructed of brick set in the American Common bond pattern of five rows of stretchers between a single row of headers and rests on a stone foundation of random ashlar bond with raised joints. The addition is punctured on each elevation with four-over-four-light double-hung sash windows. One entry door is visible on the south elevation of the stone foundation and leads to a stone patio. Two-over-two-light, arched casement windows puncture the stone foundation on the north, south, and rear (west) elevations. These windows are topped and highlighted with a stone solder course. A small, one-story, hipped roof addition, clad with random ashlar stone is attached to the north elevation of the brick addition. The west elevation of the stone addition contains a single entry door; paired, two-over-two-light casement windows are visible on the east and north elevations. One corbelled, brick, flush-end chimney is visible on the addition on the west elevations.

The interior of the dwelling was not accessible during the site visit.

Sited northeast of the dwelling is a ca. 2000, one-story, gable-front, garage/storage shed. The dwelling is clad with vertical plank siding, is topped with an asphalt shingle roof and rests on a raised concrete foundation. A single, overhead door is centered on the front, (south) elevation; one-over-one-light, double-hung sash windows are visible on the west elevation. A full-width, shed roofed porch is located on the east elevation and is supported by wood posts.

Property History

The Winter/O'Donnell House is a two-story, I-house plan dwelling typical of rural architecture in Allegany County during the first half of the nineteenth century. The dwelling is located in District 11 and is sited on lot numbers 3592, 3593, 3593, and 3594.

Architecture in the George's Creek Valley is varied. In her book *Green Glades of Sooty Gob Piles*, Donna Ware explains that domestic architecture in the first half of the nineteenth century in the George's Creek Valley was almost "exclusively vernacular in character; dwelling forms and technology were drawn from a combination of traditions that were developed in Western Maryland, as well as practices introduced by early settlers from other regions who visited or moved to the area" (Ware 1991: 63). Construction materials in the first half of the nineteenth century in Allegany County consisted of log, heavy timber frame and stone. These materials were used into the second half of the nineteenth century. By 1830, brick and vertical plank construction became a popular construction material and continued into the early twentieth century (Ware 1991: 64).

**MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM**

Continuation Sheet No. 2

AK-VI-B-031

Deed research suggests that the Winter/O'Donnell House was constructed by John Winter, who owned the property in the late 1820s. John Winter had purchased the property from Jacob Winter in September 1826 and it is assumed that the house was constructed shortly after the land purchase (Allegany Land Records, Liber W Folio 300). The construction date of the house was estimated by dating the use of the Flemish Bond pattern of the bricks on the dwelling. Flemish Bond became popular prior to the 1840s. Census records reveal that Jacob Winter was a blacksmith by trade. He was married to Margaret and had four children – John, Henry, George and Mary. John Winter, son of Jacob, was also listed as a blacksmith and was married to Hester and they had seven children – George, Ann, Elizabeth, John, Susan, Enoch and Josef.

The 1850 U.S. Census records suggest that George Winter, son of John, lived on the property by that time. George was listed as a farmer and his real estate was valued at \$5,000.00. He was married to Sarah and they had two children – Estelle and Ida. The census records also indicated that George employed two farmhands – Albert Bell and William Tracy. In 1868, the Allegany Land records confirm that the property was transferred to George's mother Hester (Allegany Land Records, Liber 27, Folio 232). Hester Winter retained the property until her death, at the time; the property was transferred back to her eldest son, George. The 1870 U.S. Census records show that George was a farmer with a real estate value of \$6,000.00 and personal assets of \$1,000.00. In 1896, the property was sold by George to his eldest sisters, Ann and Elizabeth. The sisters were joint owners until December 1902 when Ann Winter (Humbertson) sold the property to her sister Elizabeth Winter (O'Donnell) (Allegany Land Records, Liber 90, Folio 164).

The property remained in the Winter/O'Donnell family nearly 100 years until the property was sold to the Allegany Real Estate Company. The real estate company sold the property on December 17, 1943 to the Consolidation Coal Company (Allegany Land Records, Liber 198, Folio 170). The Consolidation Coal Company, later known as the Pittsburgh Consolidation Coal Company, sold the property to Maryland Coal and Realty Company on July 7, 1947 (Allegany Land Records, Liber 215, Folio 705). The property currently is owned by the Allegany Coal and Land Company (formally the Maryland Coal and Realty Company), which was established in 1987.

Assessment of Property

The Winter/O'Donnell House is one of only a few remaining examples of brick architecture dating back to the first half of the nineteenth century remaining in the area. The dwelling is an excellent example of this dwelling type and construction. The property was one of the very few farms that were able to continue their farming tradition for nearly 100 years.

The ca.1829 Winter/O'Donnell House is a significant dwelling, typical of rural brick architecture in Allegany County. The dwelling possesses the qualities of significance for domestic vernacular architecture in this area of Allegany County applying National Register Criterion C. The Winter/O'Donnell House is one of only a few remaining brick farmsteads in this area. Although the dwelling has undergone alterations over the years, including a ca. 2000 two-story rear addition, the property still retains its integrity of location, setting, materials, workmanship, feeling and association and is significant as an important architectural element to the local history of George's Creek Valley and Frostburg, Maryland.

**MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM**

Continuation Sheet No. 3

AK-VI-B-031

Works Cited

Allegany County Land Records

Var. Accessed online at MDLandRec.net on December 3, 2009.

Nelson, John, Joan Baldwin and Steve Beale

1976 Maryland Historical Trust Inventory Form for State Historic Sites Survey – Jenkins Brick House.

Personal Interview

2009 Personal interview with current owner Will Jenkins, December 7, 2009.

Scharf, J. Thomas

1882 *History of Western Maryland Being the History of Frederick, Montgomery, Carroll, Washington, Allegany, and Garrett Counties from the Earliest Period to the Present Day, Volume II.* Louis H. Everts, Philadelphia, Pennsylvania.

U.S. Department of the Interior, National Register of Historic Places, National Park Service

1991a Bulletin 16A: *Guidelines for Completing National Register of Historic Places Forms.* National Park Service, Washington, D.C.



1991b Bulletin 15: *How to Apply the National Register Criteria for Evaluation.* National Park Service, Washington, D.C.

United State Census Records

Var. Accessed online at HeritageQuest.com on December 8, 2009.

Ware, Donna, with contributions by Orlando Ridout V, Geoffrey B. Henry, and Mark R. Edwards

1991 *Green Glades and Sooty Gob Piles.* Maryland Historical Trust, Crownsville, Maryland.



12/17/2009

ISGS

a changing world

U.S. DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY




STATE OF MARYLAND
MARYLAND GEOLOGICAL SURVEY

AL-VI-B-031

winter 10' Dorell House

1998
LONACONING QUADRANGLE
MARYLAND-WEST VIRGINIA
7.5-MINUTE SERIES (TOPOGRAPHIC)



**MARYLAND HISTORICAL TRUST
NR-ELIBILITY REVIEW FORM**

Continuation Sheet No. 4

AL-VI-B-031

Photography Log

The following information is the same for each photograph:

1. MIHP # AL-VI-B-031
2. Winter/O'Donnell House
3. Allegany County, Maryland
4. Roger L. Ciuffo, R. Christopher Goodwin & Associates, Inc.
5. December 2009
6. MD SHPO

AL-VI-B-031_2009-12-07_01.tif	West elevation, looking southwest
AL-VI-B-031_2009-12-07_02.tif	Front elevation, looking west
AL-VI-B-031_2009-12-07_03.tif	Front elevation, looking northwest
AL-VI-B-031_2009-12-07_04.tif	Front elevation, looking north
AL-VI-B-031_2009-12-07_05.tif	East elevation, looking northeast
AL-VI-B-031_2009-12-07_06.tif	Rear elevation, looking south
AL-VI-B-031_2009-12-07_07.tif	Double front doors
AL-VI-B-031_2009-12-07_08.tif	Southwest corner of front elevation
AL-VI-B-031_2009-12-07_09.tif	Front elevation, brick corbel frieze
AL-VI-B-031_2009-12-07_10.tif	West elevation, chimney
AL-VI-B-031_2009-12-07_11.tif	Garage/shed, looking southwest
AL-VI-B-031_2009-12-07_12.tif	Landscape, looking northeast

Prepared by: Roger L. Ciuffo, Senior Project
Manager, R. Christopher
Goodwin & Associates, Inc.

Date Prepared: January 5, 2010



MIHP # AL-VI-B-031

Winter/o' Donnell House

Allegany County, Maryland

Roger L. Cluff, R. C. Goodwin & Associates, Inc.,
December 2009

MD SHPO - AL-VI-B-031 - 2009-12-07-1
West Elevation, Looking Southwest



MIHP # AL-VI-B-031

Winter/O'Donnell House

Allegany County, Maryland

Roger L. Cluffo, R.C. Goodman & Associates, Inc.
December 2009

MD SHPO - AL-VI-B-031 - 2009-12-07 - 2

Front elevation, looking west



MI 4P* AL-VI-B-031

Winter / O'Donnell House

Allegheny County, Maryland

Roger L. Cluffo, R.C. Goodwin & Associates, Inc.

December 2009

MD SH00 - AL-VI-B-031 - 2009-12-07-3

Front elevation, looking Northwest



MIHP # AL-VI-B-031

Winter/O'Donnell House

Allegany County, Maryland

Roger L. Clifton, R.C. Goodwin & Associates, Inc.
December 2009

MD SHPO - AL-VI-B-031 - 2009-12-07-4

front elevation, looking north



MIHP # AL-VI-B-031

winter/o'Donnell House

Allegheny County, Maryland

Roger L. Cluffo, R.C. Goodwin & Associates, Inc.,
December 2009

MD SHPO - AL-VI-B-031 - 2009-12-07-5

EAST Elevation, Looking Northeast



MIHP # AL-VI-B-031

Winter/O'Donnell House

Allegany County, Maryland

Roger L. Cluffo, R.C. Goodwin & Associates, Inc,
December 2009

MD SHPO - AL-VI-B-031 - 2009-12-07 - 6

rear elevation, looking South



MIWP # AL-UI-B-031

Winter/O'Donnell House

Allegany County, Maryland

Roger L. Cluffo, R.C. Goodwin & Associates, Inc.

December 2009

MD SHPO - AL-UI-B-031-2009-12-07-7

Double front doors



MIHP# AL-VI-B-031

Winter/O'Donnell House

Allegany County, Maryland

Roger L. Cluffo, R.C. Goodwin & Associates, Inc.

December 2009

MD SHPO - AL-VI-B-031 - 2009-12-07-8

Southwest corner of front Elevation



MIHP # AL-VI-B-031

Winter/O'Donnell House

Allegheny County, Maryland

Roger L. Cluffo, R.C. Goodwin & Associates, Inc.,
December 2009

MD SHPO - AL-VI-B-031-2009-12-07-9
Front Elevation, brick corbel frieze



MIHP # AL-UI-B-031

Winter/O'Donnell House

Allegheny County, Maryland

Roger L. Cluff, R.C. Goodwin & Associates, Inc.

December 2009

MD SHPO - AL-UI-B-031 - 2009-12-07 - 10

West elevation, chimney



MIHP # AL-VI-B-031

Winter/O'Donnell House

Allegheny County, Maryland

Roger L. Clulfo, R. C. Goodwin & Associates, Inc.

December 2009

MD SHPO - AL-VI-B-031-2009-12-07-11

Garage/shed, looking southwest



MIHP# AL-UI-B-031

Winter/O'Donnell House

Allegheny County, Maryland

Roger L. Cluffo, R.C. Goodwin & Associates, Inc.,
December 2009

MD SHPO - AL-UI-B-031 - 2009-12-07-12

landscape, looking northeast

JENKINS BRICK HOUSE

AL-VI-B-031

.3 mile south of Cabin Run Road
ca. 1830

The Jenkins Brick House is a two story, five bay wide, rectangular shaped brick structure of American Common Bond. The house is believed to have been built for John Winters in the late 1820's, soon after he had purchased the property from Jacob Winters in 1826. Although, of a subsistence nature, due to the size of the barn and the solid construction of the house, the Jenkin's farm was obviously a fine one in its day. In addition, the farm is located among an architecturally significant group of old farm houses in the upper George's Creek Valley.

MARYLAND HISTORICAL TRUST

0102675404
AL-VI-B-031

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC

Jenkins Brick House

AND/OR COMMON

2 LOCATION

STREET & NUMBER

.3 miles south of Cabin Run Road

CITY, TOWN

☒ VICINITY OF

CONGRESSIONAL DISTRICT

Sixth

STATE

Maryland

COUNTY

Allegany

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES: RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES: UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input checked="" type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME

Maryland Coal & Realty Company

Telephone #: 689-8895

STREET & NUMBER

Depot Hill

CITY, TOWN

Frostburg

☒ VICINITY OF

STATE, zip code

Maryland

21532

5 LOCATION OF LEGAL DESCRIPTIONCOURTHOUSE,
REGISTRY OF DEEDS, ETC.

Allegany County Courthouse

STREET & NUMBER

30 Washington Street

CITY, TOWN

Cumberland,

STATE

Maryland

6 REPRESENTATION IN EXISTING SURVEYS

TITLE

DATE

☐ FEDERAL ☐ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR
SURVEY RECORDS

CITY, TOWN

STATE

7 DESCRIPTION

AL-VI-B-031

CONDITION

☐ EXCELLENT
☒ GOOD
☐ FAIR

☐ DETERIORATED
☐ RUINS
☐ UNEXPOSED

CHECK ONE

☒ UNALTERED
☐ ALTERED

CHECK ONE

☒ ORIGINAL SITE
☐ MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Jenkins Brick House is a two story, five bay wide, rectangular brick structure located approximately .3 miles south of Cabin Run Road between the old and new Route 36. The facade faces southeast and is supported by a high stone foundation on the grade sloping basically south. Brick bonding consists of the American Common type and predominantly shows a characteristic pattern of five rows of stretchers between each row of headers. A beveled water table separates the brick from the stone. Double hung wooden sash frames featuring six over six lights comprise the windows in the structure; those in the rear of the house have brick jack arches over top. The facade has two entrances both with the original verticle paneled doors still intact. Transom lights are present over both doors. A unique corbeled brick frieze is found under the eaves on the front and rear of the structure. Rain gutter spoutings are set up to employ the cistern method of water storage. Replaced tin now sheathes the simple gabled roof. The facade has a five bay shed roofed porch supported by square columns and the rear of the structure has a one bay gabled roof porch. Two corbeled brick flush end chimneys also complement the house.

The Jenkins Brick House retains most all of its original fabric, currently stands in fair to good condition and is structurally sound.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input checked="" type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION			

SPECIFIC DATES ca. 1830 BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The Jenkins Farm House is a substantial building typical of rural brick architecture in Allegany County during the first half of the 19th century. In all probability the house was built for John Winters in the late 1820's. John Winters had purchased the property from Jacob Winters and family in September of 1826, and the house is believed to have been built soon after this date.¹

Judging from the size of the barn and the solid construction of the house, the Jenkin's farm was obviously a prosperous one in its day. In addition, the farm is located in the upper George's Creek Valley and is among a significant group of old farm houses located in this area, all of which were built in the late 18th and early 19th century.

The farm is presently in good condition and is the residence of a care taker for the Maryland Coal and Realty Company, who continues some grazing activities on a small scale.

1 Allegany County Land Records, Cumberland, Maryland

9 MAJOR BIBLIOGRAPHICAL REFERENCES

Allegany County Land Records, Cumberland, Maryland

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATAACREAGE OF NOMINATED PROPERTY 250 acres**VERBAL BOUNDARY DESCRIPTION**

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE

COUNTY

STATE

COUNTY

11 FORM PREPARED BY

NAME / TITLE

John Nelson, Joan Baldwin & Steve Beale

ORGANIZATION

DATE

Allegany County Historic Sites Survey12/7/76

STREET & NUMBER

TELEPHONE

507 National Highway777-8991

CITY OR TOWN

STATE

LaVale,Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

TITLE SEARCH

Jenkins Brick House
AL-VI-B-031

Allegany County Deed; Liber 215, Folio 705
grantee: Maryland Coal & Realty Company
grantor: Pittsburgh Consolidation Coal Company
July 7, 1947
Consideration: \$150,000

Allegany County Deed; Liber 198, Folio 170
grantee: Consolidation Coal Company
grantor: Allegany Real Estate
December 17, 1943

Allegany County will; Liber H, Folio 164
grantee: Elizabeth O'Donnell, (sister of Anne)
grantor: Anne Humbertson
December 2, 1902

Allegany County Deed; Liber 79, Folio 685
grantee: Elizabeth O'Donnell & Anne Humbertson
grantor: George Winter
October 5, 1896
Consideration: \$10,000.00

Allegany County Deed; Liber 27, Folio 232
grantee: Hester Winter
grantor: George Winter, et. al.
April 15, 1868

Allegany County Deed; Liber W, Folio 300
grantee: John Winters
grantor: Jacob Winter, et. al.
September 26, 1826

INVENTORY NO. A1-VI-B-031

DATE: 11/30/76

215/705

250 Acres

RECORDING: Drastic, moderate, minor

NAME OF PROPERTY: JENKINS BRICK HOUSE

LOCATION OF PROPERTY: 3 miles south of Cabin Run Rd. SOUTH OF CABIN RUN RD.

DIRECTION DWELLING FACES: (140°) Southeast

NAME OF OWNER: MARYLAND COAL + REALTY CO.

ADDRESS: DEPOT HILL, FROSTBURG 689-8885

STORIES: 1() 2(☒) 3() 4() 5() 6() BAYS: 1() 2() 3() 4(☒) 5(☒) 6() 7() ()

WINGS, ADDITIONS:

Dwelling Shape: (square, cross, rectangular)

WALL CONSTRUCTION:

- () FRAME: Bevel, clapboard, weatherboard, wood shingles, board & batten (type?)
(☒) BRICK: Bond type- common, English, Flemish. Sketch variants.
() STONE: Bond type- rubble, ashlar (random or regular), quoins-plain, rusticated
() LOG
() Other: Coverings

WALL FEATURES: BELT COURSE, PILASTERS, OTHERS

FOUNDATIONS: HIGH, LOW, BRICK, STONE

WATER TABLE: NONE, PLAIN, BEVELED, MOULDED BRICK

WINDOWS, TRIM, SHUTTERS: 1/1() 2/2() 6/6(☒) 9/6() 9/9() other()
BRICK JACK ARCH pegged() nailed() wide() narrow() mitred() pediment()

ENTRANCE, DOORS: LOCATION: 2

HARDWARE: original(☒) replaced()

FAN LIGHT, TRANSOM, SIDE LIGHTS, PLAIN

Paneled, Verticle, Horizontal Boards

CORNICE, BARGE, EAVES: (crown, fascia, soffit, bed)

original() replaced() Rafter Ends, Modillions, Dentils, Frieze,

Architrave

ROOF: GABLE FRONT, GABLE FLANK, HIP, SHED, LANSARD, GAMBREL, FLAT, BORMERS #

MATERIAL: wood shingles, slate, tin, asphalt original() replaced(☒)

PORCHES: SHAPE OF ROOF - shed(☒) hip() gable()

5 BAY FRONT END
1 BAY GABLE REAR

CHIMNEYS: NUMBER 2 BRICK(☒) STONE() CORBELLED(☒) original(☒) replaced()

LOCATION: Flush end(☒) Inside end() Outside end() Central() Interior()

ARCHES: Door and window: Keystone, Flat, Segmental, Semicircular

COMMENTS:

Use - Residence

Significance - Arch

Date Constructed - 1841

Condition - Good

SECTION VI QUADRANGLE B

STATE OF MARYLAND
MARYLAND GEOLOGICAL SURVEY


STARG (JLNC U.S. 40) 2.5 MI.

675 57°30'

676

5263 III NW (FROSTBURG)

679 55°





Jenkins Brick House

AL-VI-B-031

South of Cabin Run Road

11/30/76

John Nelson

North



Jenkins Brick House

AL-VI-B-031

South of Cabin Run Road

John Nelson

11/30/76

West